

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 1973
CONSERVATION DIVISION
Wichita, Kansas

10-9-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Jack Bowles

Complete Address 401 Local Federal Bldg., Oklahoma City, Oklahoma

Lease Name Wright Well No. 1

Location C N/2 SW Sec. 30 Twp. 21 Rge. 24 (E) (W)

County Hodgeman Total Depth 4605'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 11:00AM Day 4 Month 10 Year 1973

The above well was plugged as follows:

8 5/8" to 369' circulated w/ cement. 5 1/2" to 4604' cemented.

Top perforations 4530' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4500' Mud 4500' to 800'

Spotted 80 sacks cement 800' to 500' Mud 500' to 350'

Spotted 30 sacks cement 350' to 250' Mud 250' to 40'

Plug, Halls & 10 sacks cement 40' to 0'. Allied Pump Truck

Pulled 3506' of 5 1/2" casing.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 10/9/73
INV. NO. 7993-W

Signed: Edgar J. Lewis
Well Plugging Supervisor