


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Harvey County. Sec. 18 Twp. 22S Rge. 3W E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines _____

NW NE
Lease Owner Southern States Oil Co.
Lease Name Neufeldt #12 Well No. _____
Office Address Box 1365, Great Bend, Ks. 67530
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 12/17/80 _____ 19____
Plugging completed 12/22/80 _____ 19____
Reason for abandonment of well or producing formation _____

Depleted
If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Thompson
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3678'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	525	None
				5-1/2"	3677'	2490'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Ran sand to 3350' and 5 sacks cement. Set in floor. Had 15" stretch. Loaded hole and made shots at 2791, 2694, 2603 and 2501. Pulled 77 joints. Plugged well with 4 sacks hulls, 20 sacks gel, plug, and 175 sacks 50/50 pos 2% gel.

Plugging complete.

12-23-80

DEC 23 1980

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of December, 1980

My commission expires



Joan Kelso
Notary Public.

OPERATOR: Aladdin Petroleum Corp.
809 Petroleum Building
Wichita, Kansas 67202

LOCATION: ~~NE NE~~
NW NE
18-22s-3W
Harvey County,
Kansas

CONTRACTOR: German Drilling Company
502 Petroleum Building
Wichita, Kansas 67202

Farm: Neufeldt
Date Commenced: 9-6-65
Date Completed: 9-17-65

Well No. 12

From:	To	Formation
0	527	WOC
527	620	Lime
620	695	Lime
695	880	Lime & Shale
880	886	Red Rock
886	1100	Shale & Lime
1100	1180	Lime
1180	1445	Shale & Lime
1445	1845	Shale & Lime
1845	2069	Shale & Lime
2069	2175	Lime
2175	2255	Lime
2255	2430	Sand
2430	2468	Shale & Lime
2468	2520	Lime
2520	2588	Lime
2588	2663	Lime & Shale
2663	2748	Lime
2748	2800	Lime
2800	2877	Lime
2877	2940	Lime & Shale
2940	3045	Lime & Shale
3045	3150	Lime & Shale
3151	3169	Miss-Chat
3169	3205	Lime & Chert
3205	3244	Lime & Chert
3244	3245	Lime
3245	3298	Lime
3298	3341	Shale & Lime
3341	3391	Lime & Shale
3391	3420	Lime
3420	3450	Shale
3450	3480	Shale
3480	3525	Shale & Lime
3526	3530	Viola
3530	3548	Lime
3549	3561	Sand
3562	3564	Shale
3564	3569	Shale & Lime
3569	3596	Sand & Shale
3596	3620	Sand & Shale
3620	3628	Sand & Shale
3628	3678	Lime

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1965
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the foregoing is a true and correct copy of the Well log for the Neufeldt #1, drilled for Aladdin Petroleum Corporation and completed September 17, 1965.

GERMAN DRILLING COMPANY

Harvey F. German
Harvey F. German-Owner

Surface Pipe-525 ft. 85/8"
Production Pipe- 3677 ft. 5 1/2"

STATE OF KANSAS)
) ss.
COUNTY OF SEDGWICK)

Subscribed and sworn to, before the undersigned, a Notary Public, in and for County and State aforesaid, this seventeenth day of September, 1965.

Geneva M. German
Geneva M. German-Notary Public

My Commission expires February 28, 1968.