


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Harvey County, Sec. 18 Twp. 22 Rge. 3 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
NE NW SE
Lease Owner Southern States Oil Co.
Lease Name Friesen #2 Well No. _____
Office Address Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 7/12/79 _____ 19____
Plugging completed 7/31/79 _____ 19____
Reason for abandonment of well or producing formation _____
depleted
If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Thompson
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3661
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	506	none
				5 1/2"	3654	2304'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, had bridge at 100', worked it out. Pushed plug and ran sand, set 5 sacks cement. Loaded hole, shot pipe at 2894', 2496', 2403', 2311', pulled 73 joints. Pumped 3 sacks hulls, 10 sacks gel, 130 sacks 50-50 poz.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet) AUG 6 1979

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 24 3rd day of August, 19 79

Margaret Melcher
Notary Public.

My commission expires _____



15-079-19149-0000

OPERATOR: Aladdin Petroleum Company
Petroleum Building
Wichita 2, Kansas

LOCATION: NE-NW-SE
18-23-3W
Harvey County
Kansas

CONTRACTOR: German Drilling Company
Petroleum Building
Wichita 2, Kansas

Farm: Friesen
Date Commenced: 10-23-62
Date Completed: 11-4-62

Well No. 2
Rotary

RECEIVED
STATE CORPORATION COMMISSION
MAR - 6 1979
CONSERVATION DIVISION
Wichita, Kansas

From	To	Formation
0	55	Clay and shale
55	240	Sand
240	507	Lime and shale
507	640	Lime
640	975	Lime and shale
975	1050	Lime and shale
1050	1260	Shale and shells
1260	1660	Shale and shells
1660	1910	Shells
1910	1985	Shale and lime
1985	2075	Shale and lime
2075	2177	Lime and shale (Topeka)
2177	2245	Lime
2245	2335	Sand and shale
2335	2460	Shale and lime
2460	2517	Lime and shale
2517	2635	Lime
2635	2704	Lime
2704	2770	Lime
2770	2851	Lime
2851	2926	Lime
2926	3010	Lime
3010	3040	Lime
3040	3135	Lime and shale
3135	3150	Shale
3150	3201	Lime and Chert (Mississippi)
3201	3235	Lime and Chert
3235	3241	Lime
3241	3303	Shale
3303	3360	Shale and lime
3360	3390	Shale
3390	3507	Lime
3507	3514	Sand
3514	3535	Sand
3535	3537½	Sand
3537½	3543	Sand
3543	3559	Shale
3559	3580	Shale
3580	3601	Sand and shale
3601	3630	Lime
3630	3655	Lime
3655	3661	Total Depth

I Hereby certify that the foregoing is a true and correct copy of the Well Log for the Friesen #2, drilled for Aladdin Petroleum Company and completed November 4th, 1962.

GERMAN DRILLING COMPANY

Harvey F. German
Harvey F. German-Owner

State Of Kansas)
County of Butler)

ss.

SUBSCRIBED AND SWORN TO, before the Undersigned a Notary Public, in and for County and State aforesaid this sixth day of November, 1962.

Goneva M. German
Goneva M. German-Notary Public

My commission expires December 29th, 1963.