

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-20404-0000

LEASE NAME Soeken-Besthorn

WELL NUMBER #4

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4950 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 9 TWP. 22 RGE. 13 (E) or (W)

COUNTY Stafford

LEASE OPERATOR Woodman-Iannitti Oil Co.

ADDRESS Box 308, Great Bend, Kansas 67530

PHONE 316-792-1922 OPERATORS LICENSE NO. 6588

Date Well Completed 2-27-72

Character of Well Oil

Plugging Commenced 9-22-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-5-89

The plugging proposal was approved on 9-22-89 and 10-3-89 (date)

by Mike Wilson-Dan Goodrow and Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached? With application

Producing Formation Depth to Top Bottom T.D. 3621'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8-5/8" | 278' | None |
| | | | | 5-1/2" | 3620' | 2,965.55' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3460' and 5 sacks cement. Shot casing at 2950. Pulled 94 joints of 5 1/2" casing. B.J. Titan plugged well with 400# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls and 100 sacks 60/40 pozmix cement with 6% gel, Maximum pressure was 650 psi and shutin 300 psi.

10-10-89

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Woodman-Iannitti Oil Co. OCT 10 1989

STATE OF Kansas COUNTY OF Barton, ss. CONSERVATION DIVISION
Wichita Kansas

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold
Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 9th day of October, 1989

My Commission Expires:

STATE NOTARY PUBLIC
KANSAS
IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 9-26-91

Iona M. Leatherman
Notary Public