

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-00341-0000

LEASE NAME Soeken-Besthorn

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4290 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 9 TWP. 22 RGE. 13 (E) or (W)

COUNTY Stafford

Date Well Completed 7-17-86

Plugging Commenced 8-17-89

Plugging Completed 10-5-89

LEASE OPERATOR Woodman-Iannitti Oil Co.

ADDRESS Box 308, Great Bend, Ks. 67530

PHONE # 316-792-1922 OPERATORS LICENSE NO. 6588

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 23, 1989 (date)

by Dan Goodrow and Duane Rankin (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3789'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	277'	None
				5-1/2"	3780'	2,390.47'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. Dumped sand to 3450' and 5 sacks cement. Shot casing at 3200', 2800', 2200', 2100' and 2000'. Pulled 78 joints of 5-1/2" casing. B.J. Titan plugged well with 400# hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 100# hulls and 100 sacks 60/40 pozmix cement with 6% gel. Maximum pressure was 500 psi and shutin 250 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Ks. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Woodman-Iannitti Oil Co.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of


above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold
Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 9th day of October, 1989

My Commission Expires:



Notary Public

WELL LOG

15.185.00341-0000

COMPANY Petroleum, Inc.

SEC. 9 T. 22S R. 13W

FARM SOEKEN-BESTHORN NO. 1


LOC. SE NE NW
990' FNL
2310' FWL

TOTAL DEPTH 3785'

COUNTY Stafford

COMM. January 28, 1956 COMP. February 8, 1956

CONTRACTOR Garvey Drilling Company



CASING 8-5/8" @ 277' w/225 sax
5-1/2" @ 3780' w/100 sax

ELEVATION 1895' DF
1897' RB

PRODUCTION Lansing

FIGURES INDICATE BOTTOM OF FORMATIONS

254	Clay, Sand & Gravel
340	Shale
755	Shale, Shells, Red Bed
780	Anhydrite
1800	Shale & Shells
2595	Lime & Shale
2755	Shale & Shells
2900	Shale
3025	Lime & Shale
3115	Lime
3155	Lime & Shale
3300	Lime
3360	Shale
3595	Lime
3648	Lime & Shale
3655	Conglomerate
3710	Viola
3730	Simpson
3774	Shale & Sand
3785	Arbuckle

Sample Tops

Heebner	3236	(-1339)
Toronto	3257	(-1360)
Brn Lime	3364	(-1467)
Lansing	3383	(-1486)
BKC	3593	(-1696)
Viola	3657	(-1760)
Simpson	3721	(-1824)
Arbuckle	3778	(-1881)

RTD 3785'

RECEIVED
STATE CORPORATION COMMISSION
NOV 20 1970
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of SEDGWICK } ss:

I, Karl E. Becker of Petroleum, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the SOEKEN-BESTHORN #1 well

Karl E. Becker

Subscribed and sworn to before me this 10th day of February 19 56

My Commission Expires: September 2, 1959

Frances Sloan
NOTARY PUBLIC
FRANCES SLOAN, Notary Public
My Commission expires Sept. 2, 1959