


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Stafford County, Sec. 9 Twp. 22S Rge. 13 <sup>XY</sup>/<sub>W</sub>  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines  
SE NE NE

Lease Owner George A. Reed  
Lease Name Drach Well No. 1  
Office Address 535 Fourth Financial Center Wichita, Kans. 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plat

Dry hole  
Date Well completed Feb. 28 19 81  
Application for plugging filed Feb. 28 19 81  
Application for plugging approved Feb. 28 19 81  
Plugging commenced 10:30 A.M. Feb. 28 19 81  
Plugging completed 11:30 A.M. Feb. 28 19 81  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation Depth to top Bottom Total Depth of Well 3845'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

60 sx. at 480'  
10 sx. at 40'  
5 sx. in rathole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor

STATE OF Kansas COUNTY OF Barton, ss.  
Don Popp (employee of owner) or ~~(owner or operator)~~  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Popp  
Don POPP Holsington, Kans.  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of March, 19 81

BESSIE M. DEWERFF  
STATE NOTARY PUBLIC  
BARTON COUNTY, KANSAS  
MY COM. EXPIRES 5-20-81

My commission expires

Bessie M. DeWerff  
Bessie M. DeWerff Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 12 1981 3-12-81

CONSERVATION DIVISION  
Wichita, Kansas

DRILLERS WELL LOG

L. D. DRILLING, INC., - CONTRACTOR

GEORGE REED - OPERATOR

DRACH # 1  
SE NE NE  
Sec. 9-22-13  
Stafford County, Kans.

T. D. 3845'  
ELEV. 1896'

COMMENCED: 2-21-81  
COMPLETED: 2-28-81

CASING:

8 5/8" set at 314'

CEMENT:

W/300 sx. 50/50 Pozmix, 2% Gel, 3% CC

<u>FORMATION</u>	<u>Depth-Sample</u>	<u>Depth-Log</u>	<u>DATUM</u>
Anhydrite	750'	-	+1146
Base Anhydrite	775'	-	+1121
Heebner	3244'	3240'	-1344
Toronto	3257'	3256'	-1360
Douglas	3277'	3277'	-1381
Brown Lime	3368'	3368'	-1472
Lansing	3387'	3387'	-1491
Base Kansas City	3602'	3600'	-1704
Conglomerate	3638'	3638'	-1742
Viola	3665'	3665'	-1769
Simpson Shale	3723'	3723'	-1827
Arbuckle	3775'	3774'	-1878
TOTAL DEPTH	3845'	3845'	-1949

State of Kansas )  
County of Barton ) ss

I certify that this is a true and correct copy of the above log to the best of my knowledge.

L. D. DRILLING, INC.

Don Popp  
Don Popp

Sworn to and subscribed before me this 10th day of March 1981.

My appointment expires: 5-20-81

Bessie M. DeWerff  
Bessie M. DeWerff, Notary Public

BESSIE M. DEWERFF  
STATE NOTARY PUBLIC  
BARTON COUNTY, KANSAS  
MY APPT. EXP. 5-20-81

RECEIVED  
STATE CORPORATION COMMISSION

MAR 12 1981

CONSERVATION DIVISION  
Wichita, Kansas