

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County. Sec. 9 Twp. 22 Rge. (E) 13(W)

Location as "NE/CNW/SW" or footage from lines NW NE SW  
Lease Owner Tennessee Gas Transmission Company  
Lease Name J. L. Pieper Well No. 1  
Office Address Box 513 - Chase, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed April 28 19 57  
Application for plugging filed April 28 19 57  
Application for plugging approved April 28 19 57  
Plugging commenced April 28 19 57  
Plugging completed April 28 19 57  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bundege  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3830 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	395'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 240'; plug set with 20 sacks cement and 1/3 sack of hulls. Second plug set at 20' with 5 sacks of cement and 1/3 sack of hulls.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.  
Address P. O. Box 355 - Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Jim B. McWilliams (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim B. McWilliams  
P. O. Box 355 - Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of April, 19 57

My commission expires November 21, 1957

Mary O. Johnson  
Notary Public.  
5-4-57

PLUGGING  
FILE SEC. 9 T. 22 R. 13W  
BOOK PAGE 9 LINE 24

DRILLERS LOG

#1 J. L. Pieper

CASING RECORD:

395' (13 joints) of  
8-5/8" surface casing  
cemented @391' with  
325 sacks cement, 2%  
Calcium Chloride

COMPANY:

Tennessee Gas  
Transmission Co.

LOCATION:

NW NE SW  
Section 9-22S-13W  
Stafford County,  
Kansas

CONTRACTOR:

Strata Drilling, Inc.

COMMENCED:

April 17, 1957

ELEVATION:

1901' KB  
1898' DF  
1896' GL

COMPLETED:

April 28, 1957

TOTAL DEPTH:

D. & A.

3830'

FORMATION

FROM

TO

REMARKS

Surface soil and sand	0	175
Shale and sand	175	285
Red Bed, Shale and shells	285	386
Red Bed	386	754
Anhydrite	754	777
Shale and shells	777	1655
Lime and Shale	1655	3509
Lime	3509	3640
Lime and chert	3640	3685
Shale, Lime and Chert	3685	3775
Lime	3775	3825

Ran Halliburton Guard Log

TOTAL DEPTH 3825' KB

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

*J. B. McWilliams*  
JIM B. McWILLIAMS, Secy-Treas.

Subscribed and sworn to before me this 30th day of April, 1957.

*Mary C. Johnson*  
Notary Public

My Commission expires:  
November 21, 1959

RECEIVED  
COMMISSION

PLUGGING  
FILE SEC 9 1 22 13W  
BOOK PAGE 9 24

