

1 010039

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,253-0000

NW NW NW, SEC. 1, T 22 S, R 12 W/EX
4950 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5318

Lease Name M. Helmers Well # 6

Operator: Broken Hill Properties

County Stafford

Name & Address: P. O. Box 1201

Well Total Depth 3594 ^{116.81} feet

Wichita, KS 67201

Conductor Pipe: Size ⁴ feet

Surface Casing: Size 8 5/8 feet 602

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 25 Month: October Year: 19 85

Plugging proposal received from Darrell Kelso

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3584' Perfs at 3556-57' - Top cement 2284' tubing & cement left in hole
Cemented tubing and packer in from 3594' up to 2284'

Squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release
8 5/8" plug and pump 150 sx cement.

Plugging Proposal Received by Robert B. Tarbutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:00 pm Day: 25 Month: October Year: 19 85

ACTUAL PLUGGING REPORT Squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel,
1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

Maximum pressure 500 psi and shut in 350 psi

Remarks: Recovered 2100' 5 1/2" casing. Cemented by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE NOV 4 1985

INV. NO. 10875

RECEIVED

NOV 1 1985

CONSERVATION DIVISION
Wichita, Kansas

Signed *Robert B. Tarbutton*
(TECHNICIAN)