

To: 1 120764 12-22  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- NA 15-185-11148-0000 88 P  
SW SE NW, SEC. 1, T 22 S, R 12 W&E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3613

2970 feet from S section line  
3630 feet from E section line

Operator: Hallwood Petroleum, Inc.  
Name & Address: P.O. Box 378111  
Denver, CO 80237-8111

Lease Name Helmers Well # 4  
County Stafford

Well Total Depth 3567 115.93 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 262

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Hallwood Petroleum, Inc. License Number 3613

Address P.O. Box 378111, Denver, CO 80237-8111

Company to plug at: Hour: 8:30 a.m. Day: 22 Month: 12 Year: 19 92

Plugging proposal received from George Hutton

(company name) Hallwood Petroleum, Inc. (phone) 316-792-2756

were: 4 1/2" at 3558' w/150 sx cement, PBSD 3510', Perfs at 3300-04, 3349-54, 3382-84, 3410-12'  
1st plug sand back to 3250' and dump 4 sx cement on top of sand through bailer,  
2nd plug perforate anhydrite, squeeze through tubing, fill with 60/40 Pozmix 6% gel,  
circulate to surface.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 22 Month: 12 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3232' and perforated 4 1/2" casing at 585'. Ran tubing to 3200' and pumped 30 sx cement. Laid down 7 joints of tubing and pumped in 16 sx gel. Laid down tubing and pumped 4 sx gel and 180 sx cement to 6131' Commission  
Cement circulated in 4 1/2" casing and 4 1/2" X 8 5/8" annulus.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 29 1992  
12-29-92  
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
(if additional description is necessary, use BACK of this form.)

INVOICED  
I (could) observe this plugging.

DATE 1-12-93 2-24-93 Signed \_\_\_\_\_ (TECHNICIAN)

INV. NO. 37191 12-22-92 FEB 24 1993