

1052324

TO: STATE CORPORATION COMMISSION

1-7-99 API NUMBER 15-185-20,574-0000
C N/2 NE/4 SEC. 1, T 22 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 4620 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1320 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MELLIES "C" WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY STAFFORD 120.19

OPERATOR LICENSE # 6067 WELL TOTAL DEPTH 3698 FEET

OPERATOR: ALPHA MANAGEMENT CORPORATION PRODUCTION CSG: SIZE 5 1/2" @ 3697' WITH 175 SX

NAME AND 1501 SE 66TH ST., SUITE B SURFACE CASING: SIZE 8 5/8" @ 241' WITH 200 SX

ADDRESS OKLAHOMA CITY, OK 73149

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ROCKHOLD ENGINEERING, INC LICENSE NUMBER 5111

ADDRESS PO BOX 698 GREAT BEND, KS 67530

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 07 MONTH: 07 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM JAMES ROCKHOLD

(COMPANY NAME) ROCKHOLD ENGINEERING, INC (PHONE) 316-792-2506

WERE: TUBING FISH TOP AT 2780'. TOC @ 2900. SPENT 1 DAY ATTEMPTING TO FISH TUBING.

1ST PLUG RUN TUBING TO 2759'. SPOTTED 300# HULLS AND 25 SX CEMENT. PERFORATED 5 1/2" AT

1300' AND 600'. 2ND PLUG PULLED TUBING TO 1300' PUMPED 10 SX GEL AND 40 SX CEMENT.

3RD PLUG PULLED TUBING TO 600' CIRCULATED CEMENT TO SURFACE UP 5 1/2" AND 8 5/8" X 5 1/2" ANNULAS.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 07 MONTH: 01 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG RAN TUBING TO 2759'. SPOTTED 300# HULLS AND 25 SX CEMENT. PERFORATED 5 1/2" AT

1300' AND 600'. 2ND PLUG PULLED TUBING TO 1300' PUMPED 10 SX GEL AND 40 SX CEMENT.

3RD PLUG PULLED TUBING TO 600' CIRCULATED CEMENT TO SURFACE UP 5 1/2" AND 8 5/8" X 5 1/2" ANNULAS.

USED 235 SX CEMENT TO CIRCULATE TO SURFACE.

RECEIVED
STATE CORPORATION COMMISSION
7-12-99
JUL 12 1999

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM) CONSERVATION DIVISION
Wichita Kansas

INVOICED
OBSERVE THIS PLUGGING.

SIGNED Richard M. Lacey
(TECHNICIAN) FORM CP-2/3

DATE JUL 19 1999

INV. NO. 60044

(2)