

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-12952-00-00
Spot: CE2W2NE Sec/Twnshp/Rge: 1-22S-12W
3690 feet from S Section Line, 1680 feet from E Section Line
Lease/Unit Name: MELLIES Well Number: 4
County: STAFFORD Total Vertical Depth: 3620 feet

Operator License No.: 6067

Conductor Pipe: Size feet:

Op Name: ROBERT GREENBERG DBA ALPHA MAN

Surface Casing: Size 8.625 feet: 250

\$117.65

Address: 1501 SE 66TH ST., STE B
OKLAHOMA CITY, OK 73149

Production: Size 5.5 feet: 3619

Liner: Size feet:

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/24/2001 10:00 AM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO

Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 280' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 09/24/2001 1:45 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 3348-54, 3379-86, 3394-96, 3432-34, 3443-45'. COMPANY ATTEMPTED TO CLEAN OUT WELL BORE AT EARLIER DATE. PLUGGING CONTRACTOR FOUND JUNK IN HOLE AT 2400'. SANDED TO 2350' & 5 SX CMT ON TOP WITH DUMP BAILER. PULLED CASING. RAN IN TUBING & SPOTTED PLUGS. 1ST PLUG AT 1400' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 280' WITH 200 SX CMT CIRCULATING CMT TO SURFACE. PULLED TUBING. TOPPED OFF HOLE WITH 15 SX CMT. CIRCULATING UP THE MELLIES #1 SURFACE PIPE 50' EAST.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1702' OF 5 1/2" CASING.

Plugged through: TBG

District: 01

10-01-01

Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED

INVOICED SEP 28 2001

OCT 01 2001

DATE

10-01-01

KCC WICHITA

INV. NO.

2002060686

Form CR-23

MP