

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-12953-00-00
Spot: CE2SWNE Sec/Twnshp/Rge: 1-22S-12W
3300 feet from S Section Line, 1620 feet from E Section Line
Lease/Unit Name: MELLIES Well Number: 5
County: STAFFORD Total Vertical Depth: 3602 feet

Operator License No.: 6067 Conductor Pipe: Size _____ feet: 117.07
Op Name: ROBERT GREENBERG DBA ALPHA MAN Surface Casing: Size 10.75 feet: 220
Address: 1501 SE 66TH ST., STE B Production: Size 7 feet: 3602
OKLAHOMA CITY, OK 73149 Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/26/2001 9:45 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK TO 3300'. 1ST PLUG AT 1300' WITH 75 SX CMT. 2ND PLUG AT 650' WITH 75 SX CMT. 3RD PLUG AT 250' WITH 75 SX CMT. 4TH PLUG AT 40' WITH 15 SX CMT. USE 20 SX GEL FOR SPACER.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/26/2001 3:00 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PBTD 3572'. PERFS AT 3480-88 & 3561.5-64'. SANDED BACK TO 3300' WITH 7 SX CMT. PLUG RUN 2 3/8" TUBING TO 1320', SPOT 20 SX GEL, 400# HULLS, & 75 SX CMT. NO CIRCULATION. PUMP 1600# HULLS, 30 SX GEL. PRESSURE TO 700#. NO CIRCULATION. PUMP 400# HULLS & 9 SX GEL, GOOD CIRCULATION. PUMP 50 SX CMT. PULL TO 650' PUMP 75 SX CMT. PULL TO 250' CIRCULATE CMT TO SURFACE. HOLE STAYED FULL.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1302' OF 7" CASING.

Plugged through: TBG

District: 01

9-28-01

Signed _____

(TECHNICIAN)

RECEIVED

SEP 28 2001

KCC WICHITA

INVOICED

DATE 10-01-01

INV. NO. 2002060686

SEP 27 2001

Form CR-24