

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-12951-00-01
Spot: NESWNE Sec/Twnshp/Rge: 1-22S-12W
3760 feet from S Section Line, 1720 feet from E Section Line
Lease/Unit Name: MELLIES Well Number: 2
County: STAFFORD Total Vertical Depth: 3563 feet

Operator License No.: 6067 Conductor Pipe: Size _____ feet:
Op Name: ROBERT GREENBERG DBA ALPHA MAN Surface Casing: Size 8.625 feet: 208 WITH 140 SX CMT \$115.80
Address: 1501 SE 66TH ST., STE B Production: Size 5.5 feet: 3560
OKLAHOMA CITY, OK 73149 Liner: Size _____ feet:

Well Type: EOR UIC Docket No: E19972.1 Date/Time to Plug: 10/29/2001 1:45 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: PUMP 50 SX CMT TO 3186' THROUGH TUBING. 50 SX PLUG AT 1300' THROUGH CASING. 25 SX PLUG AT 800' THROUGH CASING. 50 SX PLUG AT 600' THROUGH CASING. 40 SX PLUG AT 230' THROUGH CASING. 10 SX PLUG FROM 0-40'.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 10/29/2001 4:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PBTD 3525'. PERFS AT 3286-90, 3347-53, 3382-86, 3396-3400, 3310-13, 3430-36, 3442-45'. PUMPED 50 SX CMT ON BOTTOM THROUGH TUBING ON 10/26/01. 10/29/01: RUN 2 3/8" TUBING TO 1300' & SPOT 25 SX CMT. SPOT 25 SX CMT AT 800'. CIRCULATE CMT TO SURFACE FROM 465' TO SURFACE WITH 165 SX CMT. TOP OFF WITH 10 SX CMT. GOOD CIRCULATION DURING JOB.

Remarks: USED COMMON CEMENT BY ALLIED. RECOVERED 453' OF 5 1/2" CASING.

Plugged through: TBG

District: 01

11-20-01

Signed _____

(TECHNICIAN)

RECEIVED

NOV 02 2001

KCC WICHITA

INVOICED

DATE

11-2-01

INV. NO.

2002060897

OCT 30 2001

Form CP-273