

To: 1 051277
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-9 15-055-00387-0000
API NUMBER 15-Drill Completion Date 2/15/57

C SW, SEC. 12, T 23 S, R 34 W/E
1320 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4782
Operator: Ensign Operating Company
Name & Address: 621 17th Street, Suite 1800
Denver, CO 80293

Lease Name Kraus Well # 2
County Finney 85.15
Well Total Depth 2620 feet
Conductor Pipe: Size feet
Surface Casing: Size 10 3/4 feet 358

Abandoned Oil Well Gas Well Input Well SMD Well D&A

Other well as hereinafter indicated

Plugging Contractor Post and Mastin Well Service License Number 8438
Address P.O. Box 297, Garden City, KS 67846

Company to plug at: Hour: 11 a.m. Day: 9 Month: 3 Year: 19 90

Plugging proposal received from Reed Wacker

(company name) Ensign Operating Company (phone) 316-276-3267

were: 7" at 2619' PBD 2617' Perfs at 2550-2616' Elevation 2938' GL

1st plug circulate hole with gel and 1 sx cottonseed hulls,

Spot through tubing:

2nd plug at 2400' with 50 sx cement, 3rd plug at 1450' with 50 sx cement,

4th plug at 335' with 40 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3 p.m. Day: 9 Month: 3 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug circulated hole with gel and 1 sx hulls,

Spotted through tubing:

2nd plug at 2400' with 50 sx cement,

3rd plug at 1450' with 50 sx cement,

4th plug at 335' with 40 sx cement,

Pressured up 10 3/4" X 7" annulus to 500 psi.

NOTE: 7" circulated with 700 sx cement.

Remarks: Used 60/40 Pozmix 2% gel by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

(did / XXXXXX) observe this plugging.

DATE 3-14-90
INV. NO. 27638

Signed Richard W. Lacy
(TECHNICIAN)

RECEIVED
MAR 13 1990 03-13-90
CONSERVATION DIVISION
Wichita Kansas