

1 030669

15-055-00396-0000
API NUMBER 15- N/A

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW NE, SEC. 20, T 23 S, R 34 ~~WXX~~

2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6417

Lease Name Piney Well # 1

Operator: Champlin Petroleum Company
Name & Address: 6441 NW Grand Blvd.
Oklahoma City, OK 73116-2290

County: Finney
Well Total Depth: 2653 ^{86.27} feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 9 5/8" feet 633'

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address P. O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 5:00 pm Day: 26 Month: February Year: 19 86

Plugging proposal received from Roy Case

(company name) Champlin Petroleum (phone) 316-275-9547

were: 7" at 2649' Perfs at 2492-2638' Part in surface pipe at 150'

1st plug at 2500' with 50 sx cement 2nd plug at 1900' with 50 sx cement

3rd plug at 1000' with 50 sx cement 4th plug at 660' with 50 sx cement
solid bridge

5th plug hulls - plug at 40' -- cement to surface with 5 sx cement

Pump 25 sx cement down annulus

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 6:00 pm Day: 27 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug ran tubing to 2492' and pumped 5 sx hulls and 50 sx cement

Let stand overnight. Ran wireline and tagged cement at 2130'. 2nd plug at 1900' with 50

sx cement, 3rd plug at 1000' with 50 sx cement, 4th plug at 660' with 50 sx cement, 5th

plug at 40' with 5 sx cement, 6th plug pumped 5 sx cement down backside and pressured up

to 1000# - held.

Top of cement on 7" casing at 330'

Remarks: No recovery. Used common cement by Sargent's
(if additional description is necessary, use BACK of this form.)

I (XXXX) did not observe this plugging.

STATE CORPORATION COMMISSION

Signed Steve Durrant
(TECHNICIAN)

DATE MAR 12 1986

MAR 11 1986

INV. NO. 12914 APR 10 1986 CONSERVATION DIVISION
Wichita, Kansas