

To: 1 090704
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Completed 10/52 15-035-00378-0000
SW SW SW NE, SEC. 2, T 23 S, R 34 W/E

TECHNICIAN'S PLUGGING REPORT

7-3

Operator License / 5952
Operator: Amoco Production Company
Name:
Address P.O. Box 800, Room 924
Denver, CO 80201

2790 feet from S section line
2490 feet from E section line
Lease Name Splitter Gas Unit Well / 1
County Finney
Well Total Depth 2612 84 89 feet
Conductor Pipe: Size feet
Surface Casing: Size 10 3/4 feet 369

Abandoned Oil Well Gas Well X Input Well SMD Well D&A
Other well as hereinafter indicated

Plugging Contractor Halliburton License Number
Address

Company to plug at: Hour: 9:30 a.m. Day: 3 Month: 7 Year: 1996

Plugging proposal received from Spanky
(company name) Halliburton (phone)

were: 7" at 2526' w/300 sx cement, Open hole, Liner-5 1/2" at 2506' w/100 sx cement to 300'
1st plug fill with cement,
Check backside.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:45 a.m. Day: 3 Month: 7 Year: 1996

ACTUAL PLUGGING REPORT 1st plug pumped 4 sx hulls and 300 sx cement down 5 1/2" casing.

Maximum pressure 200 psi and shut in 0 psi.

Hooked onto 7" X 5 1/2"-would not take cement (300 psi).

Hooked onto 10 3/4" X 7"-would not take cement (300 psi).

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 10 1996
7-10-96

CONSERVATION DIVISION
WICHITA KS

Remarks: Used 65/35 Pozmix 8% gel by Halliburton. No casing recovery.
(if additional description is necessary, use BACK of this form.)

INVOICED
I did observe this plugging.

DATE 7-22-96
INV. NO. 46029

Signed [Signature] (TECHNICIAN)