

1051871 12-9
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

15-055-00808-0000
API NUMBER 15- Drilled 1953

TECHNICIAN'S PLUGGING REPORT
Operator License # 5952
Operator: Amoco Production Co.
Name & Address: P.O. Box 800, Rm. 925
Denver, CO 80201

App. C, SEC. 14, T. 23 S, R. 33 W/E
2490 feet from N 1/4 section line
2490 feet from W 1/4 section line
Lease Name Bebermeyer GU Well # 1
County Finney
Well Total Depth 2628 85.41 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 356

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton License Number _____

Address _____

Company to plug at: Hour: 9 a.m. Day: 9 Month: 12 Year: 19 94

Plugging proposal received from Joe Eudey

(company name) Amoco Production Co. (phone) 316-356-6959

were: 6 5/8" at 2620' w/800 sx cement, Perfs at 2560-2602'
1st plug pump 2 sx hulls and 40 sx cement at perfs,

2nd plug at 1250' with 35 sx cement,

3rd plug perforate at 700' and circulate to surface.

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 13 1994
12-13 94
CONSERVATION DIVISION
WICHITA, KS

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:35 p.m. Day: 9 Month: 12 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 40 sx cement through tubing at 2576',

2nd plug pulled tubing to 1250' and spotted 35 sx cement. Perforated at 650', couldn't pump in, perforated at 450', couldn't pump in, perforated at 335', couldn't pump in.

Tried to pump down 10 3/4" and blew out at 500 psi. 3rd plug ran tubing to 650' inside 6 5/8" and circulated cement to 0'. Placed mud spacers between all plugs.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 1-3-95

INV. NO. 41939

12-9

Signed Richard W. Lucas (TECHNICIAN)