

To: 1 020308  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION 150'  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4-17-90  
15-055-00793-0000  
API NUMBER 15-Drill Completion Date 11/8/52  
200' W &

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4782  
Operator: Ensign Operating Company  
Name & Address: 621 17th Street, Suite 1800  
Denver, CO 80293

S of C, SEC. 3, T 23 S, R 33 W/R  
2490 feet from S section line  
2840 feet from E section line  
Lease Name J.J. Meyer Well # 1  
County Finney 8427  
Well Total Depth 2593 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 336

Abandoned Oil Well Gas Well  Input Well SWD Well D&A  
Other well as hereinafter indicated

Plugging Contractor Ensign Operating Company License Number 4782  
Address 621 17th Street, Suite 1800, Denver, CO 80293

Company to plug at: Hour: 9:30 a.m. Day: 17 Month: 4 Year: 19 90

Plugging proposal received from Reed Wacker

(company name) Ensign Operating Company (phone) 316-276-3267

were: 5 1/2" at 2573' Perfs at 2514-2552, 2573-2593' Tubing sanded in to 1588'  
1st plug pump 100 sx cement at 1598',  
2nd plug pump 50 sx cement at 1450',  
3rd plug pump 35 sx cement at 335',  
4th plug pump 100 sx cement down 5 1/2" X 8 5/8" annulus.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part None

Operations Completed: Hour: 11:45 a.m. Day: 17 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 100 sx cement at 1563',  
2nd plug circulated cement to surface from 340'.  
8 5/8" was full to surface.

RECEIVED  
Remarks: Used 60/40 Pozmix by Halliburton. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 5-3-90  
INV. NO. 28021  
observe this plugging.  
CONSERVATION DIVISION  
Wichita, Kansas  
04-23-90

Signed John R. Barber  
(TECHNICIAN)