

1090660

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- Completed 4/29/53
NE NE SW, SEC. 2, T 23 S, R 33 WXX
2440 feet from S section line
3170 feet from E section line

3-25

TECHNICIAN'S PLUGGING REPORT
Operator License # 5952
Operator: Amoco Production Company
Name:
Address: P.O. Box 800, Room 924
Denver, CO 80201

Lease Name Pearce Gas Unit Well # 1
County Finney
Well Total Depth 2589 84.14 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 335

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number _____
Address: _____

Company to plug at: Hour: 10:50 a.m. Day: 25 Month: 3 Year: 1996

Plugging proposal received from Bill Chatham
(company name) Amoco Production Company (phone) 316-356-6939

Work: 7" at 2580' w/750 sx cement, Open hole 2400-2589', 4 1/2" liner from 0-2400', cement to 0'
1st plug fill 4 1/2" with 4 sx hulls and cement.

RECEIVED
STATE CORPORATION COMMISSION

03-27-96
MAR 27 1996

Check annulus. _____

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by _____
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:00 p.m. Day: 25 Month: 3 Year: 1996

ACTUAL PLUGGING REPORT 1st plug pumped 400 lbs. hulls and 143 sx cement down 4 1/2".

Shut in 0 psi.

2nd plug hooked onto 4 1/2" X 7" and pumped 112 sx cement. Shut in 100 psi.

3rd plug pumped 10 sx cement down 7" X 10 3/4". Shut in 150 psi.

Remarks: Used 65/35 Pozmix Class C cement. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If desired by contractor) observe this plugging.

DATE MAR 28 1996
INV. NO. 45136

Signed _____
(TECHNICIAN)