

1 060871

15-055-20157-0000

54 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- N/A  
C NW, SEC. 34, T 23 S, R 31 W/E  
3960 feet from S section line  
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9151

Lease Name Wells Well # 1

Operator: Marden Producing Company

County Finney 88.24

Name & Address 3025 Quail St.

Well Total Depth 2715 feet

Lakewood, CO 80215

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 321

Abandoned Oil Well Gas Well  Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Hembree Well Service, Inc. License Number 6907

Address 302 E. Sycamore, Box 458, Ness City, KS 67560

Company to plug at: Hour: 8:10 p.m. Day: 11 Month: 9 Year: 19 86

Plugging proposal received from Steve Marden

(company name) Marden Producing Company (phone) 303-237-3295

were: 4 1/2" at 2713' Perfs at 2668-86' Elevation 2875' GL

1st plug sand back to 2600' and dump 5 sx cement on top of sand through bailer

2nd plug pump 200 sx down 4 1/2" (start with 75 sx cement, 2 sx hulls, 125 sx cement)

Pump 100 sx cement down backside.

Plugging Proposal Received by Don Ubel (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part None

Operations Completed: Hour: 10:30 p.m. Day: 11 Month: 9 Year: 19 86

ACTUAL PLUGGING REPORT Tagged and drilled and washed @ 1668' on metal.

1st plug pumped 85 sx cement @ 1667' through tubing.

2nd plug pumped 150 sx cement down annulus and shut in @ 300 pounds.

3rd plug filled 4 1/2" with cement and pumped 1 sx hulls mixed in 65 sx cement with the hulls scattered in the first sacks cement. Shut in at 450 pounds.

Remarks: Used 60/40 Pozmix 6% gel by Dowell. (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 9-17-86

09-15-86 SEP 15 1986

Signed Paul A. Luther (TECHNICIAN)

INV. NO. 14958

9-11 OCT 13 1986 NOV 14 1986