

1 120173

12-5

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,893-~~0000~~
NW NW SW, SEC. 2, T 23 S, R 14 W&K

TECHNICIAN'S PLUGGING REPORT

2310 feet from S section line
4950 feet from E section line

Operator License # 6588

Lease Name Copeland Well # 2

Operator: Woodman-Iannitti Oil Company

County Stafford 128.77

Name & Address Box 308

Well Total Depth 3962 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 216

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 3 p.m. Day: 5 Month: 12 Year: 19 88

Plugging proposal received from Dick Iannitti

(company name) Woodman-Iannitti Oil Company (phone) 316-792-1922

were: 5 1/2" at 3961' w/ 125 sx cement PBD 3952' Perfs at 3635-38'

1st plug sand back to 3580' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

12-9-88

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All CONSERVATION DIVISION Wichita, Kansas None _____

Operations Completed: Hour: 4:30 p.m. Day: 5 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back 5 1/2" casing back to 3585' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Pumping pressure 0-400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 1998' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-12-88

INV. NO. 2333

Signed _____ (TECHNICIAN)