

To: 1 052142 6-18
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 185-21,834-000 Docket #D-22,419
SW NW SW, SEC. 2, T. 23 S, R. 14 ^W

TECHNICIAN'S PLUGGING REPORT

Operator License / 6016
Operator: Condor Energy, Inc.
Name:
Address: P.O. Box 108
Great Bend, KS 67530

1650 feet from S section line
4950 feet from E section line
Lease Name Copeland Well # 1
County Stafford 132.89
Well Total Depth 4089 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 210

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well - O&A
Other well as hereinafter indicated _____ Dual completion

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 12 p.m. Day: 18 Month: 6 Year: 19 97

Plugging proposal received from Manny Boatright
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

logs: 5 1/2" at 4000' w/125 sx cement, Perfs at 3634-38', Open hole 4000'-4089'
1st plug sand back to 3580' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Scott Alberg
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3 p.m. Day: 18 Month: 6 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 3580' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 50 sx cement at 950',

3rd plug pumped 50 sx cement at 250',

4th plug pumped 10 sx cement at 40'.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1900' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

1 (date) ~~XXXXXX~~ observe this plugging.

INVOICED
DATE JUN 23 1997
INV. NO. 48386
6-18

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
KANSAS COMS
JUN 27 12:58