

3-20 218 R

To: 1 040250
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,041-0000
NW SW NW, SEC. 3, T 23 S, R 14 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 8061

3630 feet from S section line
4950 feet from E section line

Operator: Oil Producers Inc. of Kansas
Name & Address: Box 8647
Wichita, KS 67208

Lease Name Devore "C" Well # 3
County Stafford 129.94
Well Total Depth 3998 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 342

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering License Number 5111
Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 20 Month: 3 Year: 19 89

Plugging proposal received from Deacon Pulley
(company name) Rockhold Engineering (phone) 316-792-2506

were: 4 1/2" at 3996' PBD 3948' Perfs at 3644-52'
1st plug sand back to 3595' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
3-28-89

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 11:30 a.m. Day: 20 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 3595' and dumped 4 sx cement on top of sand through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.
Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2771.7' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (if desired) observe this plugging.

DATE 3-30-89
INV. NO. 24304

Signed Stephen J. Pfeiffer (TECHNICIAN)