

To: 1-120396
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-2
959-0000
API NUMBER 15- 185-21,951

C SW NW, SEC. 3, T 23 S, R 14 W/E
3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name DeVore "C" Well # 2

Operator: Oil Producers Inc. of Kansas
Name & Address: Box 8647
Wichita, KS 67202

County Stafford 130.00

Well Total Depth 4000 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 337

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11:30 a.m. Day: 2 Month: 4 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 3998'; w/210 sx cement PBDT 3976' Perfs at 3698-3726 (2 sets)

1st plug sand back to 3650' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 2 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3650' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 100 sx cement.

8 5/8" plate welded on surface casing with 2" outlet.

Pumping pressure 0-500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2219' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-17-90

INV. NO. 27861

APR 16 1990

Signed Duane Rankin (TECHNICIAN)

4-6-90

Wichita, Kansas