

To: 1 120962  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

8-26

API NUMBER 15- 185-21,854-0000  
SE NE SE, SEC. 3, T 23 21 S, R 14 W/E  
1980 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 6016

Rec'd  
9-6-94

Lease Name Allender Well # 3  
County Stafford  
Well Total Depth 3942 128.12 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 409

Operator: Condor Energy Inc.  
Name & Address  
P.O. Box 108  
Great Bend, KS 67530

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Peters Drilling Co. Inc. License Number 3400

Address P.O. Box 742, Great Bend, KS

Company to plug at: Hour: 9 a.m. Day: 26 Month: 8 Year: 19 94

Plugging proposal received from Mike Peters

(company name) Peters Drilling Co. Inc. (phone) 316-793-6721

were: 4 1/2" at 3941' w/200 sx cement, PBSD 3927', Perfs at 3647-53'

1st plug sand back to 3600' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:45 a.m. Day: 26 Month: 8 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3600' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 9 sx gel, 50 sx cement, 9 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-700 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1900' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

DATE SEP 12 1994  
41187

Signed Dawn Rankin (TECHNICIAN)