

1 080435

21348-0000

API NUMBER 15- 185-21,820

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SW SW, SEC. 3, T 23 S, R 14 ~~W 78~~

990 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name W. J. French Well # 1

Operator: Oil Producers, Inc. of Kansas
Name &

County Stafford

Address P. O. Box 8647
Wichita, KS 67208

Well Total Depth 4004 13013 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P. O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 12:00 pm Day: 24 Month: October Year: 19 85

Plugging proposal received from Brad Siroky

(company name) Oil Producers (phone) 316-682-3022

were: 4 1/2" at 4003' PBD 3850' Perfs at 3726-32'

1st plug sand back to 3675' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00 pm Day: 24 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3675' and dumped 4 sx cement on top of

sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10

sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Jack Luthi observed the plugging
(did ~~XXXXXX~~ observe this plugging.)
STATE CORPORATION COMMISSION

Signed J. A. Meyer
(TECHNICIAN)

DATE 11-1-85

NOV 1 1985

INV. NO. 10868

CONSERVATION DIVISION
Wichita, Kansas

11-1-85