

To: 1 040792  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

10-5  
API NUMBER 15- 185-22,616 22630-0000  
NE SW NW NE, SEC. 4, T 23 S, R 14 W/E  
4355 feet from S section line  
2195 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039  
Operator: L.D. Drilling  
Name & Address: RT. 1, Box 183B  
Great Bend, KS 67530

Lease Name Snyder B Well # 1  
County Stafford  
Well Total Depth 4040 131.30 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 427

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 5 Month: 10 Year: 19 93

Plugging proposal received from Charlie Stewart  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4036' w/125 sx cement, Perfs at 3725-30, 3935-45, 3940-50'  
1st plug sand back to 3675' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 10:15 a.m. Day: 5 Month: 10 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3675' and dumped 5 sx cement on top of sand  
bridge through bailer,  
2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx  
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement  
Maximum pressure 500 psi and shut in 100 psi.

OCT 11 1993  
10-11-93  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1203.9' of 5 1/2" casing.  
Additional description is necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging.  
DATE 10-13-93  
INV. NO. 38941

Signed Stephen J. Pfeifer (TECHNICIAN)