

1 120441

6-28

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 3/7/85 15-185-22150-0000

C S/2 NE, SEC. 4, T 23 S, R 14 W/E  
3300 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5280

Lease Name Fox "B" Well # 3

Operator: Harms Petroleum

County Stafford 129.68

Name & Address P.O. Box 488

Well Total Depth 3990 feet

Great Bend, KS 67530

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 459

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 28 Month: 6 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 3989' w/115 sx cement, PBTD 3371' Perfs at 3340-44'

1st plug sand back to 3290' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL - 6 1990  
Steve Miller  
CONSERVATION DIVISION  
WICHITA, KANSAS  
(TECHNICIAN)

7-6-90

Plugging Proposal Received by \_\_\_\_\_

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4 p.m. Day: 28 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3290' and dumped 5 sx cement

on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 50 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2851' of 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-9-90

Signed \_\_\_\_\_ (TECHNICIAN)

INV. NO. 28550

6-28