

To: 1 120635
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-30 244
API NUMBER 15-185-21,752-0000
SE SE NE, SEC. 4, T 23 S, R 14 W/E
2970 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30395
Operator: Iannitti Oil Company
Name & Address: P.O. Box 308
Great Bend, KS 67530

Lease Name Fox Well # B-2
County Stafford 130.65
Well Total Depth 4020 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 465

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address P.O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 11 a.m. Day: 30 Month: 9 Year: 19 91

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 4019' w/125 sx cement, Perfs at 3932-50'

1st plug sand back to 3880' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 1 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 p.m. Day: 30 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3880' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement

Pumping pressure 0-700 psi and shut in 350 psi.

OCT 03 1991
10-3-91
DIVISION

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2638' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

Signed Quand Parker (TECHNICIAN)

DATE 10-23-91

INV. NO. 33427