

1052264

TO: STATE CORPORATION COMMISSION

5-27

API NUMBER 15-185-21,589-0000  
C S/2 SW, SEC. 4, T 23 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3960 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME LINK WELL # 4

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD

OPERATOR LICENSE # 31995

WELL TOTAL DEPTH 4049 131.60 FEET

OPERATOR: CHARLES GRIFFIN

PRODUCTION CSG: SIZE 4 1/2" FEET 4049'

NAME AND 2263 N JENSSSEN

SURFACE CASING: SIZE 8 5/8" FEET 449'

ADDRESS CHICAGO, IL 60614

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR KLIMA WELL SERVICE INC. LICENSE NUMBER 7023

ADDRESS P.O. BOX 386, CLAFLIN, KS 67525-0386

COMPANY TO PLUG AT: HOUR: 3:30 PM DAY: 27 MONTH: MAY YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM BENNIE GRIFFIN

(COMPANY NAME) CHARLES GRIFFIN (PHONE) 773-477-6914

WERE: PERFORATIONS 3972'-3980' 3967'3975'

SAND BOTTOM TO 3920' AND PLACE 4 SX OF CEMENT ON TOP OF THE SAND WITH DUMP BAILOR

RECOVER PIPE AND PUMP DOWN THE SURFACE PIPE WITH:

300# COTTENSEED HULLS - 10SX GEL - 50 SX OF CEMENT - 10 SX OF GEL -100# COTTONSEED HULLS

8 5/8" WIPER PLUG - 125 SX OF CEMENT

RECOMMENDED 60/40 POZMIX 6% GEL PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:40 PM DAY: 27 MONTH: MAY YEAR: 1998

ACTUAL PLUGGING REPORT SANDED BOTTOM TO 3920' AND PLACED 2 SX OF CEMENT ON TOP OF SAND.

PUMPED PLUGS DOWN 8 5/8" SURFACE PIPE AS FOLLOWS:

300# COTTONSEED HULLS - 10 SX GEL -50 SX OF CEMENT -10 SX OF GEL -100# COTTONSEED HULLS

- 125 SX OF CEMENT

MAXIMUM PUMP PRESSURE 1000 PSIG INITIAL SHUT IN PRESSURE 450 PSIG

RECEIVED  
KANSAS CORPORATION COMMISSION  
6-3-98  
JUN 03 1998

REMARKS: USED 60/40 POZMIX 6% GEL BY HALLIBURTON RECOVERED 1900' OF 4 1/2" CASING  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey  
(TECHNICIAN)

FORM CP-2/3'

INVOICED  
DATE 6-8-98  
INV. NO. 50682  
5-27