

To: 1 120634
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-30
API NUMBER 15-185-21,258-0000 241P

SW SW NE, SEC. 4, T 23 S, R 14 W/E
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30395

Lease Name Fox Well # B-1
County Stafford 129.09

Operator: Iannitti Oil Company
Name & Address P.O. Box 308
Great Bend, KS 67530

Well Total Depth 3972 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 437

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111
Address P.O. Box 698, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 30 Month: 9 Year: 19 91

Plugging proposal received from Jim Rockhold
(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 3970.5' w/175 sx cement, PBTD 3958', Perfs at 3937-43'
1st plug sand back to 3885' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and dump 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
10-3-91
OCT 03 1991

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 10:30 a.m. Day: 30 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3885' and dumped 5 sx cement on
top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.
Pumping pressure 0-700 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2031' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby observe this plugging.

DATE 10-23-91
INV. NO. 33426

Signed Alvand Rankin (TECHNICIAN) ROOZ