

1052263

TO: STATE CORPORATION COMMISSION 5-27 API NUMBER 15-185-21,231-0006
NE SE SW, SEC. 4, T 23 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2970 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME LINK WELL # 2

TECHNICIAN'S PLUGGING REPORT COUNTY STAFFORD

OPERATOR LICENSE # 31995 WELL TOTAL DEPTH 4018 130.59 FEET

OPERATOR: CHARLES GRIFFIN PRODUCTION CSG: SIZE 4 1/2" FEET 4016'

NAME AND 2263 N JENSSEN SURFACE CASING: SIZE 8 5/8" FEET 428'

ADDRESS CHICAGO, IL 60614

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR KLIMA WELL SERVICE INC. LICENSE NUMBER 7023

ADDRESS P.O. BOX 386, CLAFLIN, KS 67525-0386

COMPANY TO PLUG AT: HOUR: 2:15 PM DAY: 27 MONTH: MAY YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM BENNIE GRIFFIN

(COMPANY NAME) CHARLES GRIFFIN (PHONE) 773-477-6914

WERE: PERFORATIONS 3939'-3954

SAND BOTTOM TO 3880' AND PLACE 4 SX OF CEMENT ON TOP OF THE SAND WITH DUMP BAILOR

RECOVER PIPE AND PUMP DOWN THE SURFACE PIPE WITH:

300# COTTENSEED HULLS - 10SX GEL - 50 SX OF CEMENT - 10 SX OF GEL -100# COTTONSEED HULLS

8 5/8" WIPER PLUG - 125 SX OF CEMENT

RECOMMENDED 60/40 POZMIX 6% GEL . PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 3:25 PM DAY: 27 MONTH: MAY YEAR: 1998

ACTUAL PLUGGING REPORT SANDED BOTTOM TO 3880' AND PLACED 2 SX OF CEMENT ON TOP OF SAND.

PUMPED PLUGS DOWN 8 5/8" SURFACE PIPE AS FOLLOWS:

300# COTTONSEED HULLS - 10 SX GEL -50 SX OF CEMENT -10 SX OF GEL -100# COTTONSEED HULLS

- 125 SX OF CEMENT

MAXIMUM PUMP PRESSURE 600 PSIG INITIAL SHUT IN PRESSURE 350 PSIG

CONSERVATION DIVISION
WICHITA, KS

REMARKS: USED 60/40 POZMIX 6% GEL BY HALLIBURTON RECOVERED 1844' OF 4 1/2" CASING
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE 6-8-98

SIGNED Richard W. Lacey
(TECHNICIAN) FORM CP-2/3'

INV. NO. 50683

5-27

RECEIVED
6-3-98
JUN 03 1998