

1 080485

15-185-10957-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 8-10-55

NW NW NE, SEC. 4, T23 S, R 14 W/E

4950 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6050

Lease Name Fox A Well # 1

Operator: Kelso Casing Pulling

County Stafford 129.32

Name & Address bought from TomKat, Ltd.

Well Total Depth 3979 feet

P. O. Box 347

Conductor Pipe: Size feet

Chase, KS 67524

Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3:00 pm Day: 6 Month: February Year: 19 86

Plugging proposal received from Mark McCabe

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3978' PBDT 3920' Perfs at 3967-68'; 3896-39'; 3688-94'; 3646-52'

1st plug sand back to 3590' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 7:30 pm Day: 6 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3590' and dumped 5 sx cement on top of

sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10

sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

RECEIVED STATE CORPORATION COMMISSION

Maximum pressure 150 psi and shut in 0

FEB 17 1986 2-17-86

Remarks: Recovered 2705' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this report)

INVOICED

observe this plugging.

DATE 1-17-86

Signed J. A. [Signature] (TECHNICIAN)

INV. NO. 12619