

1052339

9-23

TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-00693-0001
NE NE NW SEC. 4, T 23 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2970 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME OSCAR MILLER WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY STAFFORD

OPERATOR LICENSE # 32278 WELL TOTAL DEPTH 3975 129.19 FEET

OPERATOR: TENGASCO PRODUCTION CSG: SIZE 5 1/2" @ 3973' WITH 125 SX

NAME AND PO BOX 458 SURFACE CASING: SIZE 8 5/8" @ 229' WITH 178 SX

ADDRESS HAYS, KS 67601

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 BETH DRIVE, STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 1:30 PM DAY: 23 MONTH: 09 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 3653-3943.5

1ST PLUG SAND TO 3591' AND 5 SX CEMENT. PUMP PLUG THROUGH 5 1/2" CASING. 2ND PLUG AT 900'

WITH 10 SX GEL - 50 SX CEMENT. 3RD PLUG AT 270' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH

10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 23 MONTH: 09 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SAND TO 3591' AND 5 SX CEMENT. PUMP PLUG THROUGH 5 1/2" CASING. 2ND PLUG AT 900'

WITH 10 SX GEL - 50 SX CEMENT. 3RD PLUG AT 270' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH

10 SX CEMENT.

INVOICED

RECEIVED STATE CORPORATION COMMISSION

DATE 9-30-99
INV. NO. 2000060631

SEP 27 1999
9-27-99

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2012' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey
(TECHNICIAN)

FORM CP-2/3