

AFFIDAVIT OF COMPLETION FORM

ACO-1

This form shall be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: Oil gas, dry, SWD, OWWO, injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR Landmark Oil Exploration, Inc.

API NO. 15-185-21,518-0000

ADDRESS 105 S. Broadway, Suite 730
Wichita, Kansas

COUNTY Stafford

FIELD Wildcat SILVER BELL

**CONTACT PERSON Greg Cheney
PHONE (316) 265-8181

PROD. FORMATION Arbuckle

PURCHASER Koch Oil

LEASE Drach

ADDRESS P.O. Box 2256
Wichita, Kansas 67201

WELL NO. #1

WELL LOCATION NE NE NE


DRILLING CONTRACTOR White & Ellis Drilling, Inc.
ADDRESS 401 E. Douglas, Suite 500
Wichita, Kansas 67202

330 Ft. from N Line and

330 Ft. from E Line of

the NE/4SEC. 9 TWP.22S RGE.13W

PLUGGING CONTRACTOR ADDRESS



WELL PLAT

KCC
KGS
MISC
(Office Use)

TOTAL DEPTH 3772' PBTD

SPUD DATE 12/28/81 DATE COMPLETED 1/21/82

ELEV: GR 1890 DF KB 1895

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS (New) / (Used) casing.

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	10 3/4	8 5/8	10.5#	339'	50/50 Poz	250 sx.	2% Gel, 3% CC
Production	7 7/8	4 1/2	10.5#	3767'	50/50 Poz	125 sx.	18% salt, 3/4 of 1% CFR2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			2-4-82		
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used

RECEIVED
STATE CORPORATION COMMISSION
FEB 4 1982
CONSERVATION DIVISION
Wichita, Kansas

Date of first production 1/19/82 Producing method (flowing, pumping, gas lift, etc.) Pumping Gravity 30.5°

RATE OF PRODUCTION PER 24 HOURS Oil 24 Gas Water TR % Gas-oil ratio none

Disposition of gas (vented, used on lease or sold) None Perforations

**The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

Name of lowest fresh water producing stratum N/A Depth

Estimated height of cement behind Surface Pipe Circ. to surface

DV USED? No

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
Cellar Shale, Lime	0 7	7 3772		
			Anhydrite	739 (+1156)
			B. Anhydrite	764 (+1131)
			Heebner	3236 (-1341)
			Toronto	3256 (-1361)
			Douglas Sh.	3271 (-1376)
			Brown Lime	3365 (-1470)
			Lansing	3384 (-1489)
			Base K.C.	3592 (-1697)
			Conglomerate	3621 (-1726)
			Viola	3656 (-1761)
			Simpson Sh.	3709 (-1814)
			Arbuckle	3764 (-1869)
DST #1 (3496'-3520')				
30/30/30/30				
IFP 48-48#, ISIP 77#				
FFP 48-48#, FSIP 77#				
Rec. 10' mud				
DST #2 (3764'-3768')				
30/45/60/45				
IFP 38-48#, ISIP 116#				
FFP 58-67#, FSIP 106#				
Rec. 20' slightly gas oil cut mud				
62' gas & oil cut mud				
DST #3 (3764'-3772')				
30/45/60/45				
IFP 106-164#, ISIP 1061#				
FFP 232-281#, FSIP 1032#				
Rec. 1826' of gas in pipe				
556' clean gassy oil (29° gr.)				
114' froggy oil				

AFFIDAVIT

STATE OF Kansas, COUNTY OF Sedgwick SS,

Jeffrey R. Wood OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,
DEPOSES THAT HE IS owner and President (~~FORX~~(OF) Landmark Oil Exploration, Inc.
OPERATOR OF THE Drach LEASE, AND IS DULY AUTHORIZED TO MAKE
THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON
SAID LEASE HAS BEEN COMPLETED AS OF THE 21st DAY OF January, 19 82, AND THAT
ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH, NOT.

SUBSCRIBED AND SWORN BEFORE ME THIS 29th DAY OF January 19 82

(s) Jeffrey R. Wood, President
January 19 82

Georgia A. Bonat
NOTARY PUBLIC
Georgia A. Bonat

MY COMMISSION EXPIRES: 1/4/86

