


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 1 Twp. 22S Rge. 12W (E) (W)  
Location as "NE/CNW/SW" or footage from lines Nw SW NE  
Lease Owner Lawrence Supply Company  
Lease Name Meillies Meillies Well No. 3  
Office Address Box 448 - Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed January 1, 1954 19\_\_\_\_  
Application for plugging approved January 1, 1954 19\_\_\_\_  
Plugging commenced January 2 19 54  
Plugging completed January 8 19 54  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	200'	None
				4-1/2"	1928'	1928'
					3687'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with sand from 3690' to 3670' and ran 5 sacks of cement. Pumped in 25 sacks of mud and set a 10' rock bridge from 200' to 190' and ran 20 sacks of cement. Mudded hole to 40', set a 10' rock bridge and ran 10 sacks of cement. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Company  
Address Chase, Kansas

STATE OF \_\_\_\_\_, COUNTY OF \_\_\_\_\_, ss. \_\_\_\_\_ (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Lawrence Supply Co.


(Signature) Lawrence  
Box 448, Great Bend, Kans.  
(Address)

SUBSCRIBED AND SWORN to before me this 20<sup>th</sup> day of February, 1954

My commission expires October 21, 1957

Walter B. Wilson  
Notary Public.

24-7368-6 3-53-20M



RECORDED  
INDEXED  
FEB 15 1954  
CONSERVATION DIVISION  
Wichita, Kansas  
3-15-54

15-185-19454-0000

January 29, 1954

M & L Oil Co.  
211 Brown Bldg.  
Wichita 2, Kansas

Gentlemen:

Attached is material transfer slip on Mellies #3 covering pipe pulled by us.

Please forward to us a copy of the well log in order that we might complete our records with the state.

Thanks.

Yours very truly

LAWRENCE SUPPLY CO.

By

L. B. Lawrence

LBL:REL

RECEIVED  
COMMISSION  
JAN 29 1954  
REGISTRATION DIVISION  
Wichita, Kansas

Feb. 17, 1954

M. & L. Oil Co.  
Brown Bldg.  
Wichita, Kansas

Gentlemen:

In our letter of January 29th we requested a well log on your Wellies #3 in order that we might furnish same to the state for their records.

We were unable to obtain one from the Well Log Bureau, and if you have a log in your files, we would appreciate a copy in order that we may close our files on the plugging of the above well.

Yours very truly

LAWRENCE SUPPLY CO.

By

L. B. Lawrence

LB:REL

W

W