


WELL PLUGGING RECORD

FORMATION PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bitting Building Wichita, Kansas

Strike out upper line when reporting plugging of formations.

stafford County. Sec. 1 Twp. 22 Rge. (E)12 (W) Location as "NE1/4NW1/4SW1/4" or footage from lines NW SE SW Lease Owner Shawver-Graham, Inc. Lease Name Helmers Well No. 2 Office Address 204 N. Market, Wichita, Kansas Character of Well (completed as Oil, Gas or Dry Hole) Dry Date well completed March 22, 1949 Application for plugging filed March 24, 1949 Application for plugging approved March 24, 1949 Plugging commenced March 22, 1949 Plugging completed March 22, 1949 Reason for abandonment of well or producing formation Dry Hole If a producing well is abandoned, date of last production 19. Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well C. D. Stough Producing formation Depth to top Bottom Total Depth of Well Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Formation (blank), Content (blank), From (blank), To (blank), Size 8 5/8, Put In 175', Pulled Out None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 175' - Bridged at 175' 10 sacks cement on top of bridge Mud to 30' off bottom of cellar Bridged at 30' put 10 sacks cement to surface

APR 26 1949 4-28-49 KANSAS

(If additional description is necessary, use BACK of this sheet) Correspondence regarding this well should be addressed to Shawver-Graham, Inc. Address 204 North Market Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss. J. A. Gilliland (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland 204 N. Market, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 27th day of April, 1949

Francis R. Stingers Notary Public

My commission expires 1-29-53

PLUGGING FILE SEC-1-T-22-R-120 PAGE 28 LINE 4

HELMERS WELL NO. 2

Location: NW SE SW 1-22-12
 Stafford County, Kansas
 Commenced: 3-13-49
 Operator: Shawver-Graham, Inc.
 204 North Market
 Wichita, Kansas
 Completed: 3-22-49
 Casing Record: 175' - 8 5/8" Surface Casing
 Cemented with 175 Sack Regular

L O G

(Figures indicate bottom of formation)

Sand-Shale	175	<u>TOPS</u>	
Red Bed	400	Lansing	3271
Shells	485	Viola	3534
Red Bed - Shale	875	Simpson	3571
Shale - Shells	1400	Arbuckele	3631
Shale - Lime	1515	TD	3650
Lime	1540		
Lime - Shale	1675		
Lime	1895		
Shale - Lime	3015		
Lime	3100		
Lime - Shale	3190		
Lime - Shale	3295		
Lime	3534		
Chat - Lime	3575		
Lime - Shale	3650		
T.D.	3650		

The undersigned, Shawver-Graham, Inc., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

SHAWVER-GRAHAM, INC.

By: Dwight M. Shawver
 President

STATE COMMISSION
 KANSAS

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Be it remembered that on this 26th day of March 1949, before me the undersigned, a notary public duly commissioned in and for the county and state aforesaid, came DWIGHT M. SHAWVER, President of Shawver-Graham, Inc., a Kansas corporation, personally known to me to be such officer, and to be the same person who executed as such officer the foregoing instrument of writing in behalf of said corporation, and he duly acknowledged the execution of same for himself and for said corporation.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

My Commission Expires: 1-29-53

PLUGGING
 FILE NO. 1-27-12
 BOOK PAGE 68 LINE 4

Dwight M. Shawver
 Notary Public