


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Stafford County. Sec. 1 Twp. 22 Rge. 12 (E) W (W)
Location as "NE/CNW&SW" or footage from lines. SE SE SW
Lease Owner Morgenstern & Specter, Inc.
Lease Name Helmen "C" Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9-26-64 _____ 19____
Plugging completed 10-6-64 _____ 19____
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3580 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	265'	None
				5-1/2"	3578'	2000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3582', sanded to 3570' and dumped 5 sacks of cement @ 3570' with dump bailer. Pulled 5 1/2" casing, bailed fluid to 250', set rock bridge to 240' and dumped 20 sacks of cement @ 240'. Mudded hole to 35', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

10-16-64
RECEIVED
STATE CORPORATION COMMISSION
OCT 16 1964
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or owner/operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of October, 19 64

My commission expires May 20, 1968 Milton J. Tolson Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


COPY

Company - SHAWVER-GRAHAM, INC.
Farm - Helmers No. 1

SEC. 1 T. 22 R. 12W
SE SE SW

Total Depth. 3582
Comm. 2-20-49 Comp. 3-4-49
Shot or Treated.
Contractor.
Issued. 4-9-49

County. Stafford
KANSAS



CASING:

8 5/8" 265' cem w/200 sx.
5 1/2" 3578' cem w/60 sx.

Elevation. _____

Production. 35 bbls.

Figures indicate Bottom of Formations.

sand shale	230
redbed	595
anhydrite	625
shale, shells	1450
lime, shale	1660
lime	1775
shale, lime	2300
lime	2410
shale, lime	2770
lime sdy	2800
shale, lime	3030
lime	3085
lime, shale	3245
lime	3370
lime, shale	3383
lime	3582
Total depth	

Tops:

Brown Limestone	3231
Lansing/Kansas City	3251
Viola Limestone	3502
Simpson Formation	3530
Arbuckle Dolomite	3574

RECEIVED
STATE CORPORATION COMMISSION

OCT 7 1964

CONSERVATION DIVISION
Wichita, Kansas