

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

NORTH

Locate well correctly on above
Section Plat

Stafford County. Sec. 1 Twp. 22S Rge. 12 (E) (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW SE NE
Lease Owner PETROLEUM, INC.
Lease Name Mellies 'A' Well No. 2
Office Address 100 Derby Building Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 25, 19. 49
Application for plugging filed April 1, 19. 50
Application for plugging approved March 23, 19. 50
Plugging commenced March 10, 19. 50
Plugging completed March 17, 19. 50
Reason for abandonment of well or producing formation non-commercial

If a producing well is abandoned, date of last production March 8, 19. 50
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Arbuckle Depth to top Bottom Total Depth of Well 3595' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	250'	
				5 1/2"	3589'	2882'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled back to bottom of casing with mud. Put
5 sacks of cement at bottom of hole. Shot pipe
off at 2882'. Mudded hole to 250'. Set Rock
bridge and put 15 sacks of cement at 250'.
Finished mudding hole and put 5 sacks of cement
at top of surface.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to PETROLEUM, INC.
Address 100 Derby Building Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Eric H. Jager (employee of owner) of the above-described well,


being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Eric H. Jager
Exec. Vice-President
100 Derby Building Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of April 19. 50

My commission expires October 27, 1952.

Margerie Bradshaw
Notary Public.



APR 4 1950
4-4-50

WELL LOG

J. D. FERRELL DRILLING COMPANY, INC. &
 PETROLEUM, INC.
 MELLIES A-2

Sec. 1-T22-R12
 NW SE NE
 County: Barton

Total Depth: 3595.

Comm: 3-12-49 Comp: 3-24-49

Contractor: J.D.Ferrell Drlg.Co., Inc.

Issued: 4-1-49 Rotary O-3595

Production:

Elevation: 1800'

Casing Record: 8 5/8" 250' cemented with 175
 sax bulk cement - circulated
 5 1/2" 3589 1/2' cemented with 75 sax.

Figures indicate Bottom of Formations:

cellar	5		
sand & clay	40		
sand & shale	190		
shale & shells	800		
shale	910		
Anhydrite	950		
shale	1005		
shale & shells	1340	Tops:	
salt	1490	Topeka	2770
shale & shells	1505	Heebner	3071
shale & Lime	1810	Dodge	3090
lime	1865	Brown Lansing	3200
lime & shale	2010	Lansing	3225
lime	2115	Viola	3490
shale & lime	2355	Simpson	3591
shale & shells	2520	Arbuckle	3589
shale & lime	2710	Total Depth	3595
shale & shells	2810		
lime	2865		
lime & shale	3005		
lime	3068		
lime & Shale	3225		
lime	3595		
Total Depth-	3595		

We hereby certify this to be a correct and accurate log of the
 above described well as shown on the Daily Drilling Reports.

J.D.FERRELL DRILLING CO., INC.


By: J.W. Rallsback
 J.W. Rallsback

Subscribed and sworn to before me this 1st day of April, 1949

My Commission Expires:

October 15, 1951

Ernie V. Sandifer
 Notary Public



APR 4 1950