

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-20,574-0000

LEASE NAME Mellies "C"

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

4,620 Ft. from S Section Line

1,320 Ft. from E Section Line

LEASE OPERATOR Alpha Management Corporation

SEC. 1 TWP. 22 RGE. 12 (E) or (W)

ADDRESS 1501 S. E. 66th, Suite "B", Oklahoma City, OK 73149

COUNTY Stafford

PHONE# (405) 235-0523 OPERATORS LICENSE NO. 6067

Date Well Completed 4/4/75

Character of Well Oil

Plugging Commenced 7/7/99

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7/7/99

The plugging proposal was approved on 10/5/98 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? N/A If not, is well log attached? \_\_\_\_\_

Producing Formation Lansing-K. C. Depth to Top 3,350' Bottom 3,385' T.D. 3,700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	241'	None
				5 1/2"	3,697'	None

RECEIVED  
KANSAS CORP COM  
1999 SEP 22 A 11:00  
9-22-99

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Perforated casing at 1,300 & 600'. Ran 2 1/2" tubing to 2,749'. Allied mixed 200# hulls followed by 25 sx 60/40 pozmix with 3% calcium chloride and 6% gel blended with 100# hulls displaced to 2,100'. Pulled tubing to 1,300'. Mixed 10 sx gel followed by 40 sx 60/40 pozmix with 6% gel. Pulled tubing to 600', circulated cement to surface in 5 1/2" and 8 5/8" with 235 sx. Pulled tubing and filled to surface with 2 1/2 cubic yards of six sack sand readymix concrete.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address P. O. Box 698 Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Alpha Management Corp.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Robert Greenberg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) 1501 SE 66, Suite B  
Okla. City, OK 73149

SUBSCRIBED AND SWORN TO before me this 20th day of Sept., 19 99

My Commission Expires: Sept. 16, 2001

Notary Public  
Don Harris