

ATE OF KANSAS  
ATE CORPORATION COMMISSION  
J S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-02-3-117

15-185-12951-00-01  
API NUMBER Comp 8-1-52

LEASE NAME Mellies  
WELL NUMBER #2

11-7-01 NOV 07 2001

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

3300 Ft. from S Section Line

1650 Ft. from E Section Line

KCC WICHITA

LEASE OPERATOR ALPHA MANAGEMENT CORPORATION

SEC. 1 TWP. 22 RGE. 12W (E) or (W)

ADDRESS 1501 SE 66th, Suite B Okla. City, OK, 73149

COUNTY Stafford

PHONE # (405) 235-0523 OPERATORS LICENSE NO. 6067

Date Well Completed \_\_\_\_\_

Character of Well SWD EOR

Plugging Commenced 10-25-01

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10-29-01

This plugging proposal was approved on \_\_\_\_\_ (date)

by Scott Alberg (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 3563'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	208	None
				5-1/2"	3560'	430'
				5-3/4"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging material used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each side.  
Pulled 2 jts. of tubing, pumped 50 sacks cement down tubing and displaced to bottom, pulled rest of tubing, a total of 103 jts. 5-1/2" casing parted @430', ran tubing to 1300', pumped 25 sks. cement, pulled up to 800', pumped 5 sks. gel and 25 sks. cement, pulled up to 430', pumped 165 sks. cement and circulated to surface. Pulled tubing out and topped off with 10 sks. cement. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Alpha Management Corporation

State of Kansas County of Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 5th day of November 2001

[Signature]  
Notary Public

My Commission Expires:

