

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County, Sec. 1 Twp. 22 Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines G. N/2 NW SE

Lease Owner Graham-Messman-Rinehart Oil Company

Lease Name Helmers "A" Well No. 1

Office Address P. O. Box 1033, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed October 21 19 52

Application for plugging filed October 27 19 52

Application for plugging approved October 21 19 52

Plugging commenced October 21 19 52

Plugging completed October 22 19 52

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 148, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	170'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged hole with 20 sacks cement,
on bottom. Plug @ 170 feet with
10 sacks cement. Top plug @ 35 ft.
Mud to surface.

STATE CORPORATION COMMISSION

OCT 29 1952 10-28-52

CONSERVATION DIVISION

Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graham-Messman-Rinehart Oil Company

Address P. O. Box 1033, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick Kan, ss.

J. A. GILLILAND (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. A. Gilliland

P. O. Box 1033, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of October, 19 52

Olive Carter

Notary Public.

My commission expires March 21, 1955.

PLUGGING
FILE SEC 1 T 22R 122
BOOK PAGE 54 LINE 19

HELMERS "A" #1WELL RECORD

Location: G. N/2 NW SE Sec. 1-22-12W
Stafford County, Kansas

Operator: G-M-R Oil Company

Contractor: G-M-R Oil Company

Casing Record: 8 5/8" @ 170' w/150 sacks.

Commenced: October 12, 1952

Completed: October 21, 1952

Elevation: 1814 K.B.

Production: D & A

LOG

Sand	90
Sandstone	110
Shale	170
Shale	192
Clay Shale	568
Anhydrite	595
Shale & Shells	1005
Shale & Shells	1533
Shale-Broken Lime	1715
Lime & Shale	1870
Shale & Lime	1953
Shale & Lime	2180
Lime & Shale	2340
Shale & Lime	2476
Shale & Lime	2605
Lime & Shale	2790
Shale & Lime	2910
Shale & Lime	3020
Lime & Shale	3090
Lime & Shale	3180
Lime & Shale	3213
Lime	3263
Lime	3304
Lime	3359
Lime	3378
Lime	3416
Lime	3498
Lime-Conglomerate	3543
Conglomerate	3605 T.D.

TOPS

Heebner	-	3083	(-1269)
Br. Lime	-	3213	(-1399)
Lansing	-	3238	(-1424)
Congl.	-	3510	(-1696)

STATE CORPORATION COMMISSION

OCT 26 1952

CONSERVATION DIVISION
Wichita, Kansas

The undersigned, GRAHAM-MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

GRAHAM-MESSMAN-RINEHART OIL COMPANY

By *[Signature]*

Subscribed and sworn to before me
this 27th day of October, 1952.

[Signature]
Notary Public

My commission expires: March 21, 1955.

PLUGGING
FILE SEC 1 T 23 R 127
BOOK PAGE 576 LINE 19