

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Stafford County. Sec. 1 Twp. 22S Rge. 12 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE/4 SE/4 SE/4

Lease Owner M & L Oil Co.

Lease Name Helmers Well No. 1

Office Address Brown Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 13 19 53

Application for plugging filed (Verbal) July 13 19 53

Application for plugging approved (Verbal) July 13 19 53

Plugging commenced July 13 19 53

Plugging completed July 13 19 53

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 3601 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	225'	8 5/8"	225'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud and set
Bottom plug at 200' with 20 sacks cement and top plug
at 40' with 10 sacks cement. Filled last 6' with dirt.

7-17-53

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Birmingham-Bartlett Drilling Co.

Address 300 Kaufman Building, Wichita 2, Kansas

STATE OF Kansas COUNTY OF Sedgwick
Richard Hindery, partner of Birmingham-Bartlett Drilling Co., contractor for

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. BIRMINGHAM-BARTLETT DRILLING CO.

(Signature) By Richard Hindery partner
300 Kaufman Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of July, 19 53

My commission expires October 2, 1954 Beverly Larson Notary Public.

PLUGGING
FILE SEC-1 22S 12E
BOOK PAGE 117 LINE 34

HELMERS NO. 1 WELL

LOCATION: SE/4 SE/4 SE/4
Section 1-22S-12W
Stafford County, Kansas

SPUDED: 7-3-53
COMPLETED: 7-13-53

OWNER: M & L Oil Co.
Brown Building
Wichita, Kansas

CONTRACTOR: Birmingham-Bartlett Drilling Co.
300 Kaufman Building
Wichita, Kansas

SURFACE CASING: 8-5/8" 20# casing cemented at 225'
with 200 sacks cement and 2 cc.

OIL STRING: None set. D & A.

L O G

(Figures indicate bottom of formation)

0	80	Clay and sand
	540	Shale and red bed
	565	Anhydrite
	1050	Red bed, shale and shells
	1430	Shale and shells
	1995	Broken lime
	2085	Broken lime and shale
	2695	Shale and shells
	3265	Shale and lime
	3480	Lime
	3530	Lime and shale
	3593	Lime and chert
	3601	Shale and lime
	3601	RTD - D & A

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the formations encountered in drilling the Helmers No. 1 Well as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery

Subscribed and sworn to before me
this 14th day of July, 1953.

Wesley J. Ginger
Notary Public

My commission expires November 29, 1954

