

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-055-00396-8890  
API NUMBER Drilled 1949

LEASE NAME Piney

WELL NUMBER 1

2970 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 20 TWP. 23S RGE. 34 (W)

COUNTY Finney

Date Well Completed 1-27-50

Plugging Commenced 2-26-86

Plugging Completed 2-27-86

LEASE OPERATOR Champlin Petroleum Company

ADDRESS 6441 N. W. Grand, Oklahoma City, OK 73116

PHONE#(405) 840-5521 OPERATORS LICENSE NO. 6417

Character of Well gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? Yes if not, is well log attached? \_\_\_\_\_

Producing Formation Chase Group Depth to Top 2504' Bottom 2638' T.D. 2653'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				9-5/8"	633'	None
				7"	2644'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set. RIH w/2-3/8" on-off tool & loaded backside. Latch on RBP @ 1826'. POH w/RBP, RIH w/tbg & set @2492'. Mix 5 sx hulls & pump ahead of 50 sx cement. POH to 1390'. TIH w/wireline & tag plug @ 2130'. TIH w/tbg & pump 50 sx cement plug @ 1900'. POH to 1000' & pump 50 sx plug. POH to 660' & pump 50 sx plug. POH to 40' & pump 5 sx plug to 3'. Pump 5 sx cement in 8-5/8"x7" annulus. Pressure to 1000#, held OK. Cut off head 3' below ground level & weld on plate w/name & date.

Name of Plugging Contractor Sargents Casing Pulling License No. \_\_\_\_\_

Address P. O. Box 506, Liberal, KS 67901

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Marilyn Day (Employee of Operator) or ~~xxxxxxx~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Marilyn Day

(Address) 6441 NW Grand, Okla City, OK 73116

SUBSCRIBED AND SWORN TO before me this 11 day of April, 19 86

Notary C. Owens  
Notary Public

My Commission Expires: 10-08-87  
STATE CORPORATION COMMISSION



APR 16 1986  
4-16-86  
CONSERVATION DIVISION  
Wichita, Kansas