

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15-055-00378-8880  
 API NUMBER N/A

LEASE NAME Splitter Gas Unit

WELL NUMBER 1  
2490 Ft. from N Section Line

2490 Ft. from E Section Line

SEC. 2 TWP. 23S RGE. 34 (E) or (W)

COUNTY Finney

Date Well Completed 10-52

Plugging Commenced 7-3-96

Plugging Completed 7-3-96

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Amoco Production Company

ADDRESS PO Box 800 Room 924 Denver, CO 80201

PHONE (303) 830-5323 OPERATORS LICENSE NO. 5952

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 6, 1996 (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? \_\_\_\_\_

Producing Formation Chase Depth to Top 2526' Bottom 2612' T.D. 2612'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	Surface			10 3/4"	369'	0
	Production			7"	2526'	0
	Production Liner			5 1/2"	2506'	0
	Tubing			2 3/8"	2554'	2554'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Well was plugged using 336 sacks of 40/60 POZ with 6% Gel to fill casing from 2602' to 5' below ground level. Used 20 of cottonseed hulls in lead slurry. Cut off casing 5' below ground level and restore location.

(If additional description is necessary, use BACK of this form.)

RECEIVED  
 KANSAS CORPORATION COMMISSION

Name of Plugging Contractor Halliburton License No. \_\_\_\_\_

Address \_\_\_\_\_ 7-12-96 JUL 12 1996

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Amoco Production Company CONSERVATION DIVISION

STATE OF Colorado COUNTY OF Denver, ss. WICHITA, KS

Susan R. Potts (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Susan R. Potts

(Address) PO Box 800 Room 924 Denver, CO 80201

SUBSCRIBED AND SWORN TO before me this 10th day of July, 19 96

Dennis R. Harris  
 Notary Public

My Commission Expires: 11-10-96

15-055-00378-0000

Date: 5/6/96

Type of Operation: Plug & Abandonment

Lease and Well Number: Splitter Gas Unit No. 1

Field: Hugoton

Formation: Chase

Location: Sec 2 - T23S - R34W

TD: 2612' PBSD: 2612'

Surface Csg: 10 3/4" set @ 369', cmt w/ 200 sx circulated

Production Csg: 7" 20 ppf set @ 2526', cmt w/ 300 sx circulated

Production Liner: 5 1/2" 14 ppf set @ 2506', cmt w/ 100 sx class H Premium to 300'

Purpose: TO PxA the Subject Well

Procedure:

- 1- TOH w/ tbg, rods, and pump.
- 2- Set a cement plug to the surface w/ 450 sx of 65/35 POZ, 14.4 ppg, Class 'C' cement.  
Add 2 sx of cotton seed hulls to the first 10 sx of cement.
- 3- Cut off csg 3' below the ground and weld on steel cap w/ lease identification.
- 4- Restore the location.

Note: Please contact the KCC 48 hours prior to the scheduled date.

Procedure reviewed w/ KCC representative Steve Pfeifer on 5/6/96.

Prepared By: Sonia K. Vahedian  
Petroleum Engineer

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 08 1996

CONSERVATION DIVISION  
WICHITA, KS



ELECTRIC WELL LOG **045939**

Location 150'N & 150'E of Center	COMPANY <u>NORTHERN PUMP CO.</u>	COMPANY <u>NORTHERN PUMP CO.</u>
	FILE _____	
	WELL _____ SPLITTER # <u>1</u>	
	FIELD <u>Hugoton</u>	
	COUNTY <u>Finney</u> STATE <u>Kansas</u>	
	SEC <u>2</u> TWP <u>23 S</u> RGE <u>34 W</u>	
	SURVEY _____	
Log Measured From <u>Ground Level</u> Elevation _____	WELL _____ SPLITTER # <u>1</u>	
Drilling Measured From <u>" "</u> Elevation _____		
Permanent Datum <u>" "</u> Elevation _____		
	FIELD _____	
	County <u>Finney</u>	
	State <u>Kansas</u>	

RECEIVED  
KANSAS CORPORATION COMMISSION

MAY 08 1996

CONSERVATION DIVISION  
WICHITA, KS

15-055-00378-0000