

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-055-00808 0000

LEASE NAME Bebermeyer Gas Unit

WELL NUMBER 1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2790 Ft. from S Section Line

2790 Ft. from E Section Line

LEASE OPERATOR Amoco Production Company

SEC. 14 TWP. 23S RGE. 33 (E) or (W)

ADDRESS P O Box 800 Room 924 Denver, CO 80201

COUNTY Finney

PHONE# (303) 830-5323 OPERATORS LICENSE NO. 5952

Date Well Completed 4-15-53

Character of Well Gas

Plugging Commenced 12-6-94

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-9-94

The plugging proposal was approved on December 2, 1994 (date)

by Mr. Glen Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Chase Depth to Top 2560' Bottom 2602' T.D. 2628'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				<u>30-3/4"</u>	<u>356'</u>	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Set 40 sacks cement plug 2602 to 2170. Pump 32 bbls, 9ppg mud spacer 2170 to 1250. Set 35 sacks plug 1250 to 873. Pump 8 bbls mud spacer 873 to 650. Cement 650 to surface with 70 sacks. Cement slurry was 60/40 poz w/6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. RECEIVED

KANSAS CORPORATION COMMISSION

Address _____

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Amoco Production Company JAN 17 1995

STATE OF Colorado COUNTY OF Denver, ss. 1-17-95

CONSERVATION DIVISION
WICHITA, KS

Susan R. Potts (Employee of Operator) (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Susan R. Potts

(Address) P O Box 800 Room 924 Denver, CO 80201

SUBSCRIBED AND SWORN TO before me this 16th day of January, 19 95

Dena R. Harris
Notary Public

My Commission Expires: 11-10-96