


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County, Sec. 27 Twp. 21 Rge. 15 XX/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____

SE SW NE
Lease Owner Production, Inc.
Lease Name Bauer # 1 Well No. 1
Office Address Box 459, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Dry Hole
Date Well completed December 28 1981
Application for plugging filed December 28 1981
Application for plugging approved December 28 1981
Plugging commenced December 28 1981
Plugging completed December 28 1981
Reason for abandonment of well or producing formation _____

D & A
If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz, Stafford, Ks
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3940'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	915	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

700' 60 sx
240' 40 sx
40' 10 sx
10 sx rathole
50=50 poz 4% gel; 3%cc

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Mustang Drilling & Exploration, Gt. Bend, Ks 67530

STATE OF Kansas COUNTY OF Barton, ss.
Kenneth Roach (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth Roach
P.O. Drawer 1609, Great Bend, Ks
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of December, 19 81

My commission expires _____



Beverly Shewbart
Notary Public.
RECEIVED
STATE CORPORATION COMMISSION

1-12-82

JAN 12 1982
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS' WELL LOG

OPERATOR: Production, Inc.
Box 459, Great Bend, Kansas 67530

WELL: Bauer #1 API # 15-145-20,925

LOCATION: SE SW NE
Sec 27-T 21 S-R 15

COMMENCED: 12-18-81 COMPLETED: 12-28-81

ELEVATION: GL: 1952 DF: 1954KB: 1959 TOTAL DEPTH: 3940'

CASING: Surface: 8 5/8"; 23#; set at 915 feet;
Cemented with 425 sacks Common cement; 3% cc; 2% gel

Production: ; #; set at feet;
Cemented with sacks cement;

DEPTH:	FORMATION	FORMATION TOPS	
0 - 70	Sand	Heebner	3344
70 - 365	Sand, Clay, Shale	Toronto	3363
365 - 460	Sand	Douglas	3380
460 - 700	Redbed	Brown Lime	3453
700 - 910	Shale	Lansing	3462
910 - 919	Anhydrite	Base KC	3694
919 - 1160	Anhydrite, Shale	Viola	3788
1160 - 1960	Shale	Simpson Sand	3866
1960 - 2500	Shale, Lime	Arbuckle	3888
2500 - 2750	Lime, Shale	LTD	3937
2750 - 3290	Shale, Lime	RTD	3940
3290 - 3344	Lime, Shale		
3344 - 3348	Shale		
3348 - 3363	Lime, Shale		
3363 - 3380	Lime		
3380 - 3453	Shale		
3453 - 3462	Lime, Shale		
3462 - 3694	Lime		
3694 - 3788	Lime, Shale		
3788 - 3866	Lime		
3866 - 3888	Sand		
3888 - 3937	Dolomite		
3937	LTD		
3940	RTD		

ACKNOWLEDGEMENT

STATE OF KANSAS, COUNTY OF BARTON, ss:

Before me, the undersigned, a Notary Public, within and for said county and state, on this 30th day of December, 1981, personally appeared Kenneth Roach to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary deed for the uses and purposes therein set forth.

Subscribed and sworn to before me this 30th day of December, 1981.

STATE NOTARY PUBLIC
BEVERLY SHEWBART
 Barton County, Kansas
 My App. Exp. April 14, 1982

Kenneth Roach
Beverly Shewbart
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 DECEMBER 12 1982
 CONSERVATION DIVISION
 Wichita, Kansas