


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County. Sec. 31 Twp. 21 Rge. 15 (X) W (W)
Location as "NE/CNWxSWx" or footage from lines SW-SE-NE
Lease Owner PETROLEUM, Incorporated
Lease Name HAUSER Well No. 1
Office Address 311 East Third, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed May 11 1953
Application for plugging filed March 11 1955
Application for plugging approved March 14 1955
Plugging commenced March 23 1955
Plugging completed April 19 1955
Reason for abandonment of well or producing formation
Depletion of producible zones.
If a producing well is abandoned, date of last production March 15 1955
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. M.A. Rives, Pratt, Kansas
Producing formation Arbuckle Depth to top 3912 Bottom 3940 Total Depth of Well 3962 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	Water & Oil	3,915'	3,918'	8-5/8"	250'	NONE
				5 1/2"	3,961'	2,949'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

(Drilled cement out to a total depth of 3,941.5')

Filled hole with crushed rock from 3,941.5' to 3,900' and placed five sacks cement from 3,900' to 3,865'. Globe Oilwell Cementing, Inc. pumped down 20 sacks of Controlbar to kill Dakota water flow, and then pumped in cement from 800' to 125'. Filled surface pipe with sand and capped with cement.

STATE OF KANSAS
CONSERVATION DIVISION
Wichita, Kansas
4-27-55

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Morgan Pipe Pulling Company (License #43)
Address 108 West Second Street, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Paul B. Shivel (employee of owner) or (~~agent~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul B. Shivel
Rural Route 2, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of April, 1955
Ray E. Anderson
Notary Public.

My commission expires November 21, 1957

PLUGGING
FILE SEC 31 T 21 R 15 W
BOOK PAGE 103 LINE 33

DRILLER'S LOG HAUSER NO. 1

PETROLEUM, INC., Operator

Section 31, Twp. 21S, Rge. 15W

GARVEY DRILLING COMPANY, Contractor

Location: SW SE NE

Drilling Commenced: April 27, 1953

County: Pawnee County, Kansas

Drilling Completed: May 8, 1953

R.T.D.: 3962'

Casing Record: 8 5/8" @ 250' w/225' sax
5 1/2" @ 3961' w/75' sax

Figures below indicate bottom of formation:

130	Sand
165	Sand & Shale
250	Shale
365	Shale & Shells
405	Shale
495	Sand
950	Red Bed & Shale
983	Anhydrite
1800	Shale & Shells
3208	Lime & Shale
3800	Lime
3860	Conglomerate
3962	Lime
3962'	R.T.D.

Tops:

Heebner: 3376 (-1389)
 Brown Lime: 3488 (-1501)
 Lansing: 3500 (-1513)
 Arbuckle: 3912 (-1925)
 DST, 3910-20, open 1 hour, rec. 250'
 oil, 1175' BHP.
 DST, 3920-40, open 45 mins., rec. 65'
 heavily oil cut mud, 60' gas cut mud,
 420' water, 870' BHP.

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By W W Fisher

RECEIVED
 STATE CORPORATION COMMISSION
 APR 27 1953
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
)
 COUNTY OF SEDGWICK)

SS:

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 14th day of May, 1953.

Charlotte Heisman
 Notary Public

My commission expires: October 13, 1954.

PLUGGING
 FILE SEC 31 T 21 R 15W
 BOOK PAGE 103 LINE 33