


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County. Sec. 30 Twp. 21 Rge. 15 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
C S/2 NE
Lease Owner Benson Mineral Group, Inc.
Lease Name Zook #1 Well No. _____
Office Address Denver, Colorado 80202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6/11/79 _____ 19____
Plugging completed 6/14/79 _____ 19____
Reason for abandonment of well or producing formation _____
depleted.
If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Schmitt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3906
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	510	none
				5 1/2"	3880	1659'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Put control head on. Rigged up and shot pipe at 1933', 1854', 1756', 1659', pulled 42 joints. Sun Cementing plugged well with 1 sack hulls, 14 sacks gel, released plug and pumped 150 sacks 50-50 pos, 6% gel.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet) JUN 18 1979

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

1-18-79
CONSERVATION DIVISION
WICHITA, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of June, 19 79

Margaret Melcher
Notary Public.

My commission expires _____



Operator

Benson Mineral Group, Inc.

15-145-20499-0000

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No.

1

Lease Name

Zook

S 30 T 21 S R 5 W W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
sand	0	20		
clay	20	50		
salt & shale	50	384		
Dakota sand	384	479		
shale & red bed	479	820		
shale	820	960		
anhydrite	960	985		
red bed	985	1800		
shale	1800	1960		
doromite	1960	2040		
lime & shale	2040	3400		
shale	3400	3450		
lime	3450	3850		
sand & shale	3850	3906		

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1979

CONSERVATION DIVISION
Wichita, Kansas

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Title

Date