


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County, Sec. 30 Twp. 21 Rge. 15 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines SE NE SE
Lease Owner Sam P. Wallingford, Inc.
Lease Name Unruh Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 12-1-61 19____
Plugging completed 12-4-61 19____
Reason for abandonment of well or producing formation Depleted.



If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Lackamp
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4000 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	924'	None
				5-1/2"	3962'	3024'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3910', ran 500 lbs. of sand to 3850' and dumped 5 sacks of cement @ 3850' with dump bailer. Pulled casing to 600' and pumped in 10 sacks of mud to casing. Pulled balance of 5 1/2" casing, bailed fluid to 200' set 10' rock bridge to 190' and dumped 35 sacks of cement @ 190'. Mudded to 35', set 5' rock bridge to 30' and ran 10 sacks of cement to base of cellar. 12-18-61

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
DEC 18 1961
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.
Noel J. Knight (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 1961

My commission expires May 20, 1964 Milton J. Volin Notary Public.



ROTARY DRILLING LOG

OPERATOR: McKnab Production Company, Inc.
 UNRUM NO. 1
 SW NE SE Sec. 30-21-15N
 Pawnee County, Kansas

CONTRACTOR: Capitt Drilling, Inc.
 COME: 4/1/58
 COMP: 4/16/58

Remarks: Set 8-5/8" surface casing
 at 924' cemented with 450 sacks
 bulk cement, 2% C.C.

FORMATIONS:

Sand	37'
Shale & Shells & Sand	309'
Shale	330'
Sand	430'
Red Bed	660'
Red Bed & Shale	924'
Red Bed, Shale & Shells	1400'
Shale & Shells	1830'
Lime & Shale	2158'
Lime	2290'
Lime & Shale Streaks	2449'
Lime & Shale	2520'
Shale & Lime	2754'
Shale & Lime Streaks	2850'
Lime	2900'
Lime & Shale	2990'
Lime	3390'
Shale & Lime	3455'
Lime	3772'
Lime & Shale	3796'
Conglomerate (Cherty)	3838'
Lime	3871'
Arbuckle	4000'
Rotary Total Depth	4000'

Set 5-1/2" oil string at 3964'
 cemented with 100 sacks common
 cement.

We certify the above log is true
 and correct to the best of our
 knowledge and belief.

CAPITT DRILLING, INC.

R.R. McNicol

R. R. McNicol

RECEIVED
 STATE OIL & GAS COMMISSION
 APR 23 1958
 OIL & GAS DIVISION